Geophysical Research Abstracts Vol. 19, EGU2017-14558, 2017 EGU General Assembly 2017 © Author(s) 2017. CC Attribution 3.0 License.



## Geomorphic monitoring of two dam removals in northern Iberian Peninsula: methodology, results and lessons learned

Askoa Ibisate (1), Alfredo Ollero (2), Daniel Ballarín (2), Jesús Horacio (3), Daniel Mora (4), Amaia Mesanza (5), Carles Ferrer-Boix (6), Vanesa Acín (7), David Granado (7), and Juan Pedro Martín-Vide (8)

(1) University of the Basque Country, Geography, Prehistory and Archaeology, Vitoria-Gasteiz, Spain (askoa.ibisate@ehu.es), (2) University of Zaragoza, Geography and Land Management Department, Spain, (3) University of Santiago de Compostela, Laboratorio de Tecnoloxía Ambiental, Spain, (4) MASTERGEO, S.L., Spain, (5) University of the Basque Country, Mining and Metallurgical Engineering and Materials Science, Topography Section, Spain, (6) University of British Columbia, Geography, Canada, (7) ECOTER, S.C., Spain, (8) Technical University of Catalonia, Hydraulic, Maritime and Environmental Engineering, Spain

The methodology and results of two dam removals in two different rivers is presented and compared. One removed all-at-once and the second one in a four-stage removal process. Methodology included topographical measurements of the channel, TLS measurements of river bed and bars and sediment grain size and transport. Morphological channel adjustments occurred mainly shortly after dam removals, but with differences among the one removed instantaneously, that was immediate, whereas that conducted by stages that took longer. Degradational processes were observed upstream of both dams, but also aggradational processes (pool filling) upstream of one of them. Flood events reactivated incision and bank erosion, whereas longitudinal profile recovery, grain-size sorting and upstream erosion took longer, especially in that removed in stages, where one year after is total removal its maximum potential erosion attained just the closest reach to the dam and knickpoint upstream migration was still adapting to the new base level position. Lessons learned helped to improve a third in process dam removal geomorphological monitoring, including an improved sediment transport and bank retreat monitoring.